

Gefco 30K Speedstar Reconditioned 2013

SPECIFICATIONS RIG 151

Engine	Cummins ISX 420 HP
Derrick	• 30' Gefco mast rated @ 50,000Lbs 29ft stroke
Pullback (Hook load)	• 30,000LBS
Top Drive	• 5,833 ft-lbs. torque
	Hydrostatic/Planetary top head drive
Top Drive Speed	• 0-130RPM
Down Push	• 25,000LBS
Mud Pump	• 5x6 Gardner Denver FXG 200gpm. @200psi
Main Winch (Single line)	• 25,000 LBS x 3/4" wire rope
Wire Line	• 8000 LBS x 1/4" non rotating wire rope
Air compressor	Sullair 900cfm/350psi

TOOLING

Drill Pipe	CP-HD Core pipe as required
Breakout System	Hydraulic Petol chain tongs
Casing Running Equipment	• HIR 5 1/2 ", 7'', 8 5/8", 9 5/8" Casing elevators
	Top drive casing circulating and cementing heads
Wireline Coring	• 4 5/8" CP-HD Core pipe or 6 5/8"
	• CP-HD 3 m 3" core barrel with two 2 7/8" inner bbl. 1.5m
	barrel with 6" core
	Christensen overshot core retrieval assembly

SUPPORT FOUIPMENT

30FFORT EQUIPMENT	
Generator	• 20 KW 490/208v Stamford generators / Light tower Light tower with (4) 1000-watt halogen lights
Boiler	 30HP Williams and Davis 120 psi 2002 Sterling LT9500 Truck Mounted 2400 L fuel tank 5000 L water tank
Core Van	 IHC 4300 series 24' Cube van box 12' Core mark table 12'-Fold down work platform 4' x 8' Dry crew change area
Pipe Truck	Kenworth T300 with Cassady hydraulic pipe arm, angle capable



TEL.: 403-912-1947 273159 RGE RD 14, ROCKYVIEW COUNTY, AB T4B 4S1